



#	Desc	Type	Value	Area (SF)	Fill (CY)	Cut (CY)	Bank	Compacted	Expanded	Chg/.1 Ft
▼ 1	Topsoil	TSR	0.33	51,084	2,116		1,002	891	1,168	189
						Topsoil	7	5	10	
						Sand	717	624	825	
						Clay	278	261	333	
						Rock	0	0	0	
▼ 2	Paving	DPT	0.92	75,726	3,013		3,296	2,991	3,879	280
						Topsoil	0	0	0	
						Sand	1,536	1,336	1,766	
						Clay	1,761	1,655	2,113	
						Rock	0	0	0	
▶ 5	Riprap	DPT	0.5	1,442	43		10	9	11	5
▶ 6	Sidewalk	DPT	0.92	7,050	366		195	176	229	26
▶ 7	Island	TSR	0.33	24,353	2,142		727	663	857	90
▼ 9	Building	EL	1073	14,057	3,762		4	3	4	52
						Topsoil	0	0	0	
						Sand	2	2	3	
						Clay	1	1	2	
						Rock	0	0	0	
▶ 10	Pavers	DPT	1	1,745	5		135	122	158	6
▶ 12	Dumpster	DPT	1.5	989	0		199	184	237	4
▶ 22	Teller	DPT	1	335	55		0	0	0	1
▶ 46	Sidewalk	DPT	0.92	4,040	11		333	295	387	15
▶ All				180,821	11,513		5,902	5,333	6,931	670